DOOR SCHEDULES

DOOR NO	DOOR SIZE			DOOR TYPE	FRAME TYPE	DETAILS			LABEL (MIN)	HARD-WARE	LOUVER (WxH)	NAMEPLATE	NOTES
	WIDTH	HEIGHT	THK			HEAD	JAMB	SILL					
100A	6' - 0"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
100B	6' - 0"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
102A	3' - 0"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
102B	3' - 0"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
104	3' - 0"	7' - 0"	0' - 2"	WOOD									
105	3' - 0"	7' - 0"	0' - 1 1/2"	WOOD									
106	3' - 0"	7' - 0"	0' - 1 1/2"	WOOD									
107	3' - 0"	7' - 0"	0' - 1 1/2"	WOOD									
108	3' - 10 1/2"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
109	3' - 0"	7' - 0"	0' - 1 1/2"	WOOD									
110	3' - 0"	7' - 0"	0' - 1 1/2"	WOOD									
111	3' - 0"	7' - 0"	0' - 1 1/2"	WOOD									
114A	6' - 0"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
114B	6' - 0"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
115A	3' - 0"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
115B	3' - 0"	7' - 0"	0' - 2"	ALUMINIUM STOREFRONT									
116	3' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
117	3' - 0"	7' - 0"	0' - 2"	WOOD									
119	3' - 0"	7' - 0"	0' - 2"	WOOD									
120	3' - 0"	7' - 0"	0' - 2"	WOOD WITH LOUVERS									
121	3' - 0"	7' - 0"	0' - 2"	WOOD WITH LOUVERS									
122	3' - 0"	7' - 0"	0' - 2"	WOOD WITH LOUVERS									
123	3' - 0"	7' - 0"	0' - 2"	WOOD									
124	3' - 0"	7' - 0"	0' - 2"	WOOD									
125	3' - 0"	7' - 0"	0' - 2"	WOOD									
126A	3' - 0"	7' - 0"	0' - 2"	WOOD									
126B	3' - 0"	7' - 0"	0' - 2"	WOOD									
128	3' - 0"	7' - 0"	0' - 2"	WOOD									
129A	3' - 0"	7' - 0"	0' - 2"	WOOD									
129B	3' - 0"	7' - 0"	0' - 2"	WOOD									
130	3' - 0"	7' - 0"	0' - 2"	WOOD									
131	6' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
132	6' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
133	3' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
134	3' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
135	6' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
136	6' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
137	6' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
139A	6' - 0"	7' - 0"	0' - 2"	WOOD									
139B	6' - 0"	8' - 0"	0' - 2"	HOLLOW METAL									
139C	6' - 0"	8' - 0"	0' - 2"	HOLLOW METAL									
139D	6' - 0"	8' - 0"	0' - 2"	HOLLOW METAL									
139E	6' - 0"	8' - 0"	0' - 2"	HOLLOW METAL									
139F	6' - 0"	8' - 0"	0' - 2"	HOLLOW METAL									
140A	3' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
140B	8' - 0"	14' - 0"	0' - 2"	SECTIONAL O.H.									
140C	8' - 0"	14' - 0"	0' - 2"	SECTIONAL O.H.									
141	3' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									
143	3' - 0"	7' - 0"	0' - 2"	HOLLOW METAL									

WALLER TODD & SADLER
ARCHITECTS
1909 CYPRESS AVENUE
VIRGINIA BEACH, VA 23451
(757) 417 - 0140

30%
SUBMITTAL
06 OCT. 2009

US Army Corps of Engineers
Norfolk District

REV	DATE	DESCRIPTION	BY	APP

DESIGNED: Designer
DRAWN: Author
CHECKED: Checker
SUBMITTED:
PROJECT NO. #####
DRAWING NO.
Last worked on:
File name:
DATE: 06 OCT. 2009
SCALE: AS NOTED
NORFOLK DISTRICT FILE NO.
SPECIFICATION NO.
Plot scale: 1:1

NORFOLK DISTRICT
CORPS OF ENGINEERS
NORFOLK, VIRGINIA

RFP
SUBMITTAL
06 OCT. 2009

CENTRAL ISSUE FACILITY

DOOR SCHEDULE

A-601
SHEET OF ###

10/6/2009 3:08:30 PM
C:\Revit Projects\Central Issue Facility_Tim Brown.rvt